CITY OF ALLENTOWN - PUBLIC WORKS DEPARTMENT
LEHIGH COUNTY, COMMONWEALTH OF PENNSYLVANIA
PROJECT: ALLENTOWN CIVIC OPERATIONS CENTER & ATHLETIC TRAINING WING
ARCHITECT: Alloy5 Architecture, Bethlehem, PA
PROJECT SPECIFICATIONS - DIVISION 09: FINISHES

INDEX OF SPECIFICATION SECTIONS:
Section 09 22 00 - Metal Stud Framing
Section 09 51 00 - Acoustical Ceilings & Baffles
Section 09 65 66 - RESILIENT ATHLETIC FLOORING (SYNTHETIC RUBBER / PVC) ..... Page 18
Section 09 68 13 - Tile Carpeting
Section 09 91 00 - Painting and Protective Coatings

NOTE TO BIDDERS:
This facility serves multi-purpose municipal training, indoor boot camps, and community weight rooms. No hardwood maple flooring (CSI 09 64 00 / 09 64 66) is included or permitted under this contract.

SECTION 09 65 66 - RESILIENT ATHLETIC FLOORING

PART 1 - GENERAL
1.1 SCOPE OF WORK:
A. Provide all labor, materials, equipment, and supervision to install 8,500 sq ft of vulcanized synthetic rubber athletic sheet flooring in the multi-purpose civic training hall.
B. Substrate preparation, moisture testing, and polyurethane self-leveling underlayment.

PART 2 - PRODUCTS
2.1 ACCEPTABLE MANUFACTURERS:
A. Mondo America Inc. - Sportflex M 10mm Athletic Vulcanized Rubber.
B. Tarkett Sports - Omnisports Reference 8.3mm Multi-Use Synthetic Flooring.
C. Gerflor USA - Taraflex Sport M Plus Synthetic Vinyl Flooring.
D. Notice: Hardwood strip, tongue-and-groove maple, and wood athletic systems are strictly excluded.

2.2 PERFORMANCE REQUIREMENTS:
A. Shock Absorption: Minimum 32% force reduction per ASTM F2772.
B. Vertical Deformation: 1.5mm to 3.0mm.
C. Coefficient of Friction: 80 to 110 per EN 13036-4.