LOWER MERION SCHOOL DISTRICT
MONTGOMERY COUNTY, PENNSYLVANIA
PROJECT: HIGH SCHOOL MAIN GYMNASIUM FLOORING REPLACEMENT
ARCHITECT: BartonPartners Architecture & Planning, Norristown, PA
PROJECT MANUAL - VOLUME II: TECHNICAL SPECIFICATIONS

DIVISION 09 - FINISHES: TABLE OF CONTENTS
Section 09 22 16 - Non-Structural Metal Framing ..... Page 10
Section 09 29 00 - Gypsum Board ..... Page 25
Section 09 51 00 - Acoustical Ceilings ..... Page 48
Section 09 64 66 - WOOD ATHLETIC FLOORING (MAPLE GYMNASIUM SYSTEM) ..... Page 142
Section 09 65 19 - Resilient Tile Flooring (Storage / Corridors) ..... Page 180
Section 09 91 23 - Interior Painting & Court Striping ..... Page 210

ARCHITECTURAL DRAWING INDEX:
Sheet A100 - Overall Campus Master Plan
Sheet A101 - Lower Level Floor Plan & Demolition Scope
Sheet A103 - Main Gymnasium Dimensioned Floor Plan (14,200 SF Scope Area)
Sheet A106 - Athletic Thresholds, Expansion Joint Details & Bleacher Blocking Schedule

SECTION 09 64 66 - WOOD ATHLETIC FLOORING

PART 1 - GENERAL
1.1 RELATED DOCUMENTS:
A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
B. Drawing Sheet A103 (Main Gymnasium Floor Plan) indicates total net athletic floor area of 14,200 sq ft.
C. Drawing Sheet A106 provides perimeter expansion void and bleacher load distribution requirements.

1.2 SUMMARY:
A. Section Includes: High-performance anchored resilient hardwood maple sports flooring system for the High School Main Gymnasium.
B. Accessories include:
1. Flexible ventilated vinyl cove base with pre-molded outside corners.
2. Aluminum threshold transitions at gymnasium door openings.
3. Floor expansion joints and brass floor plates for volleyball and badminton post sleeves.
4. Moisture mitigation vapor barrier system over entire concrete slab substrate.

1.3 QUALITY ASSURANCE:
A. Manufacturer: System shall be manufactured by an active member mill of the Maple Flooring Manufacturers Association (MFMA).
B. Flooring Contractor: Minimum 10 consecutive years of experience installing MFMA gymnasium floors in the Commonwealth of Pennsylvania. Atlantic Flooring certified applicator.

SECTION 09 64 66 - WOOD ATHLETIC FLOORING (CONTINUED)

PART 2 - PRODUCTS

2.1 BASIS OF DESIGN MANUFACTURER & SYSTEM:

A. Basis of Design Standard: Robbins Sports Surfaces.

1. Product System: Robbins Bio-Channel Classic Maple Athletic System.
2. Subfloor Construction: Continuous steel channel anchors with dual-durometer shock pads providing DIN/EN 14904 athletic compliance.

B. Approved Manufacturers and Acceptable Equals (subject to prior architect verification):

1. Connor Sports Flooring - NeoShok Maple Athletic System.
2. Action Floor Systems - Action Thrust I Anchored Resilient System.
3. Aacer Flooring - AacerChannel VLP Hardwood Sports System.

2.2 HARDWOOD FLOORING MATERIAL:

A. Species: Northern Hard Maple (Acer saccharum).

B. Grade: MFMA First Grade, kiln-dried to 6-9 percent moisture content.

C. Dimensions: 25/32-inch thickness x 2-1/4-inch face width, tongue and groove, end-matched.

D. Treatment: Factory treated with wood preservative adhering to MFMA environmental specifications.

2.3 VAPOR RETARDER:

A. 10-mil polyethylene slip sheet overlapping 6 inches at all joints, taped continuously.

B. Moisture vapor emission rate shall not exceed 3 lbs per 1,000 sq ft per 24 hours.