PAVILION CENTRAL SCHOOL DISTRICT
GENESEE COUNTY, NEW YORK
CAPITAL IMPROVEMENT PROGRAM: HIGH SCHOOL GYMNASIUM RESTORATION
ARCHITECT: Kimmel Bogrette Architecture + Site, Blue Bell, PA / Rochester, NY
PROJECT MANUAL - SPECIFICATION SECTION 09 64 00

PROJECT SUMMARY & SCOPE:
Sanding, screening, sealing, athletic court painting, and heavy-duty polyurethane finish coating for the High School Gymnasium (approx. 10,214 sq ft).
Reference QuickBooks Master Estimate # 3790.
Target Completion Window: Summer Recess 2027 (June 25 - August 15, 2027).

SECTION 09 64 00 - HARDWOOD FLOOR SANDING & ATHLETIC REFINISHING

PART 1 - GENERAL
1.1 SECTION INCLUDES:
A. Heavy drum sanding of existing 10,214 SF maple gymnasium floor down to bare wood.
B. Screening, tack rag cleaning, and application of MFMA approved athletic sealer.
C. Layout, masking, and precision painting of NCAA regulation game lines and center court school logo.
D. Application of two (2) finish coats of high-solids, MFMA certified polyurethane sports floor finish.

PART 2 - PRODUCTS
2.1 BASIS OF DESIGN FINISH SYSTEM:
A. Bona US - Bona SuperCourt Athletic Finishing System.
  1. Bona SuperCourt Athletic Sealer (low-VOC penetrating seal).
  2. Bona SuperCourt Optum High-Performance Polyurethane Sports Finish.
B. Acceptable Equal: Robbins Sports Surfaces - MFMA Heavy Duty Gym Finish.

PART 3 - EXECUTION
3.1 DRUM SANDING & LEVELING:
A. Machine sand entire 10,214 sq ft floor with heavy riding or walk-behind drum sanders.
B. First cut: #36 grit paper diagonal to grain to level all high spots.
C. Second cut: #60 grit paper parallel with wood grain.
D. Third cut: #100 grit finish paper to provide smooth uniform surface.